No.	Status	Date
HIS-2006-0412	Issued	2006-02-24

UT Thickness Survey - ATU-100 Full Unit

Scope and Objectives

This report details the 10-year full-unit ultrasonic thickness survey conducted at the Hamilton Plant for ATU-100. The scope encompasses all piping circuits defined in QSCP-IP-ATU100 Rev 0, including Class 1, Class 2, and Class 3 systems. This survey fulfills the 10-year interval requirements for Class 2 and Class 3 piping and the 5-year interval for Class 1 systems, ensuring compliance with API 570 and ASME B31.3 design standards.

The primary objective is to assess the current wall thickness at 118 established CMLs to determine corrosion rates and remaining life. Kevin Doucette performed the field measurements and data analysis, while Anil Rao provided the technical review and oversight for the inspection program. All activities were executed to verify the integrity of the pressure boundary against the retirement thickness limits specified for each line.

Inspection Methodology and Calibration

Ultrasonic thickness measurements were performed under QSCP-NDT-001 Rev 0 and HIS-UT-002 Rev 1. The inspection utilized a Krautkramer DMS 2 0317, which was verified against HIS-CAL-06-012 prior to use. All NDE personnel are qualified in accordance with ASNT SNT-TC-1A to ensure technical competency in data acquisition and interpretation.

The survey followed the procedures outlined in ASTM E797 for manual pulse-echo measurements. Surface preparation was conducted at each CML to ensure adequate acoustic coupling. Data was compared against LNDE-RPT-96-014 for long-term corrosion rate calculations and LNDE-RPT-01-037 for short-term rate assessments in Class 1 and rich amine systems.

Class 1 and Sour Gas Systems

The Class 1 sour gas inlet lines 6-SG-101 and 6-SG-102, designed for 1965 kPa(g) at 66 °C, were inspected at all designated CMLs. These A106 Gr.B lines have a nominal thickness of 7.11 mm and a retirement limit of 3.56 mm. Current readings indicate stable wall conditions with no immediate threats to integrity identified during this 5-year cycle.

Regenerator overhead lines 3-RV-101 and 2-RV-102 were also surveyed. These lines operate under a design pressure of 345 kPa(g) at 121 °C. Despite the corrosive nature of the service, the measured thicknesses remain well above the t-min values of 3.56 mm and 2.79 mm respectively, consistent with the historical data recorded in LNDE-RPT-01-037.

Amine and Reflux Systems

Rich amine lines 4-RA-101, 4-RA-102, and the header 6-RA-103 were prioritized due to their design limits of 862 kPa(g) and 82 °C. The 6-RA-103 header, with a nominal thickness of 10.97 mm and t-min of 4.57 mm, showed no significant localized thinning. Similarly, lean amine supply lines 4-LA-101, 4-LA-102, and header 6-LA-103 remain within acceptable limits for the 2413 kPa(g) design pressure.

Stainless steel reflux lines 3-RF-101 and 2-RF-102, constructed of A312 TP316, were inspected for general thinning. The L/R exchanger lines 4-LA-104 and 4-RA-104 were also evaluated, with 4-LA-104 designed for the highest unit temperature of 138 °C. All amine and reflux circuits meet the criteria for continued service under the Class 2 ten-year interval.

Utility and Auxiliary Systems

Class 3 utility systems, including reboiler steam line 2-ST-101 and amine cooler cooling water lines 3-CW-101 and 3-CW-102, were surveyed as part of the full-unit scope. The 2-ST-101 line, designed for 1034 kPa(g) at 186 °C, showed minimal wall loss compared to the 3.91 mm nominal thickness. The cooling water lines remain significantly above their 2.79 mm retirement thickness.

Treated gas line 8-TG-101 was inspected at all CMLs. With a design pressure of 1896 kPa(g) and a t-min of 4.06 mm, the line shows high remaining life. The results for all Class 3 systems confirm that the 10-year inspection frequency remains appropriate based on the low corrosion rates observed since the baseline survey in LNDE-RPT-96-014.

Thickness readings, measured 2006-02-24

Line 6-SG-101 | Sour gas inlet | A106 Gr.B | t_nom 7.11 mm | t-min 3.56 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-SG-101-01	7.11	3.56	2001-03-02	6.82	6.59	0.053	0.046	>50	2011-02-24	
6-SG-101-02	7.11	3.56	2001-03-02	6.71	6.51	0.054	0.040	>50	2011-02-24	
6-SG-101-03	7.11	3.56	2001-03-02	6.74	6.42	0.066	0.064	43.2	2011-02-24	
6-SG-101-04	7.11	3.56	2001-03-02	6.73	6.28	0.081	0.090	30.1	2011-02-24	
6-SG-101-05	7.11	3.56	2001-03-02	6.68	6.22	0.092	0.092	28.8	2011-02-24	
6-SG-101-06	7.11	3.56	2001-03-02	6.87	6.49	0.058	0.076	38.4	2011-02-24	

Line 6-SG-102 | Sour gas inlet | A106 Gr.B | t_nom 7.11 mm | t-min 3.56 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-SG-102-01	7.11	3.56	2001-03-02	6.72	6.26	0.088	0.092	29.2	2011-02-24	
6-SG-102-02	7.11	3.56	2001-03-02	6.72	6.25	0.086	0.094	28.5	2011-02-24	
6-SG-102-03	7.11	3.56	2001-03-02	6.69	6.26	0.078	0.086	31.3	2011-02-24	
6-SG-102-04	7.11	3.56	2001-03-02	6.64	6.22	0.077	0.084	31.6	2011-02-24	
6-SG-102-05	7.11	3.56	2001-03-02	6.93	6.72	0.041	0.042	>50	2011-02-24	

Line 8-TG-101 | Treated gas | A106 Gr.B | t_nom 8.18 mm | t-min 4.06 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
8-TG-101-01	8.18	4.06	1996-03-08	8.20	7.89	0.031	0.031	>50	2016-02-24	
8-TG-101-02	8.18	4.06	1996-03-08	8.20	7.75	0.045	0.045	>50	2016-02-24	
8-TG-101-03	8.18	4.06	1996-03-08	8.23	7.79	0.044	0.044	>50	2016-02-24	
8-TG-101-04	8.18	4.06	1996-03-08	8.10	7.76	0.034	0.034	>50	2016-02-24	
8-TG-101-05	8.18	4.06	1996-03-08	8.22	7.95	0.027	0.027	>50	2016-02-24	

Line 4-LA-101 | Lean amine supply | A106 Gr.B | t_nom 6.02 mm | t-min 3.18 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-LA-101-01	6.02	3.18	1996-03-08	5.99	5.51	0.048	0.048	48.4	2016-02-24	
4-LA-101-02	6.02	3.18	1996-03-08	6.01	5.76	0.025	0.025	>50	2016-02-24	
4-LA-101-03	6.02	3.18	1996-03-08	5.96	5.76	0.020	0.020	>50	2016-02-24	
4-LA-101-04	6.02	3.18	1996-03-08	6.07	5.78	0.029	0.029	>50	2016-02-24	
4-LA-101-05	6.02	3.18	1996-03-08	6.01	5.81	0.020	0.020	>50	2016-02-24	
4-LA-101-06	6.02	3.18	1996-03-08	6.06	5.64	0.042	0.042	>50	2016-02-24	
4-LA-101-07	6.02	3.18	1996-03-08	5.99	5.57	0.042	0.042	>50	2016-02-24	

Line 4-LA-102 | Lean amine supply | A106 Gr.B | t_nom 6.02 mm | t-min 3.18 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-LA-102-01	6.02	3.18	1996-03-08	6.02	5.63	0.039	0.039	>50	2016-02-24	
4-LA-102-02	6.02	3.18	1996-03-08	6.07	5.67	0.040	0.040	>50	2016-02-24	
4-LA-102-03	6.02	3.18	1996-03-08	6.07	5.55	0.052	0.052	45.4	2016-02-24	
4-LA-102-04	6.02	3.18	1996-03-08	5.99	5.34	0.065	0.065	33.1	2016-02-24	
4-LA-102-05	6.02	3.18	1996-03-08	6.00	5.62	0.038	0.038	>50	2016-02-24	
4-LA-102-06	6.02	3.18	1996-03-08	6.00	5.83	0.017	0.017	>50	2016-02-24	
4-LA-102-07	6.02	3.18	1996-03-08	6.00	5.63	0.037	0.037	>50	2016-02-24	

Line 6-LA-103 | Lean amine header | A106 Gr.B | t_nom 7.11 mm | t-min 3.56 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-LA-103-01	7.11	3.56	1996-03-08	7.02	6.75	0.027	0.027	>50	2016-02-24	
6-LA-103-02	7.11	3.56	1996-03-08	7.19	6.87	0.032	0.032	>50	2016-02-24	
6-LA-103-03	7.11	3.56	1996-03-08	7.08	6.65	0.043	0.043	>50	2016-02-24	

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-LA-103-04	7.11	3.56	1996-03-08	7.17	6.52	0.065	0.065	45.4	2016-02-24	
6-LA-103-05	7.11	3.56	1996-03-08	7.19	6.49	0.070	0.070	41.7	2016-02-24	
6-LA-103-06	7.11	3.56	1996-03-08	7.16	6.42	0.074	0.074	38.5	2016-02-24	
6-LA-103-07	7.11	3.56	1996-03-08	7.18	6.76	0.042	0.042	>50	2016-02-24	
6-LA-103-08	7.11	3.56	1996-03-08	7.04	6.79	0.025	0.025	>50	2016-02-24	

Line 4-RA-101 | Rich amine | A106 Gr.B | t_nom 8.56 mm | t-min 3.81 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-RA-101-01	8.56	3.81	2001-03-02	8.39	8.27	0.025	0.024	>50	2016-02-24	
4-RA-101-02	8.56	3.81	2001-03-02	8.45	8.27	0.027	0.036	>50	2016-02-24	
4-RA-101-03	8.56	3.81	2001-03-02	8.42	8.10	0.051	0.064	>50	2016-02-24	
4-RA-101-04	8.56	3.81	2001-03-02	8.37	8.34	0.029	0.006	>50	2016-02-24	
4-RA-101-05	8.56	3.81	2001-03-02	8.42	8.29	0.031	0.026	>50	2016-02-24	
4-RA-101-07	8.56	3.81	2001-03-02	8.51	8.30	0.030	0.042	>50	2016-02-24	
4-RA-101-08	8.56	3.81	2001-03-02	8.30	8.07	0.061	0.046	>50	2016-02-24	
4-RA-101-09	8.56	3.81	2001-03-02	8.43	8.43	0.014	0.000	>50	2016-02-24	
4-RA-101-10	8.56	3.81	2001-03-02	8.48	8.27	0.040	0.042	>50	2016-02-24	
4-RA-101-11	8.56	3.81	2001-03-02	8.39	8.14	0.054	0.050	>50	2016-02-24	

Line 4-RA-102 | Rich amine | A106 Gr.B | t_nom 8.56 mm | t-min 3.81 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-RA-102-01	8.56	3.81	2001-03-02	8.48	8.41	0.013	0.014	>50	2016-02-24	
4-RA-102-02	8.56	3.81	2001-03-02	8.50	8.15	0.042	0.070	>50	2016-02-24	
4-RA-102-03	8.56	3.81	2001-03-02	8.37	8.27	0.029	0.020	>50	2016-02-24	
4-RA-102-04	8.56	3.81	2001-03-02	8.35	8.24	0.030	0.022	>50	2016-02-24	
4-RA-102-05	8.56	3.81	2001-03-02	8.36	8.19	0.036	0.034	>50	2016-02-24	
4-RA-102-06	8.56	3.81	2001-03-02	8.38	8.15	0.036	0.046	>50	2016-02-24	
4-RA-102-07	8.56	3.81	2001-03-02	8.49	8.29	0.029	0.040	>50	2016-02-24	
4-RA-102-08	8.56	3.81	2001-03-02	8.36	8.05	0.044	0.062	>50	2016-02-24	
4-RA-102-09	8.56	3.81	2001-03-02	8.35	8.18	0.037	0.034	>50	2016-02-24	

Line 6-RA-103 | Rich amine header | A106 Gr.B | t_nom 10.97 mm | t-min 4.57 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-RA-103-01	10.97	4.57	2001-03-02	10.82	10.76	0.024	0.012	>50	2016-02-24	
6-RA-103-02	10.97	4.57	2001-03-02	10.69	10.50	0.059	0.038	>50	2016-02-24	
6-RA-103-03	10.97	4.57	2001-03-02	10.84	10.67	0.032	0.034	>50	2016-02-24	
6-RA-103-04	10.97	4.57	2001-03-02	10.59	10.40	0.058	0.038	>50	2016-02-24	
6-RA-103-05	10.97	4.57	2001-03-02	10.61	10.34	0.061	0.054	>50	2016-02-24	
6-RA-103-06	10.97	4.57	2001-03-02	10.86	10.74	0.027	0.024	>50	2016-02-24	
6-RA-103-07	10.97	4.57	2001-03-02	10.79	10.66	0.033	0.026	>50	2016-02-24	
6-RA-103-08	10.97	4.57	2001-03-02	10.83	10.58	0.039	0.050	>50	2016-02-24	
6-RA-103-09	10.97	4.57	2001-03-02	10.85	10.67	0.034	0.036	>50	2016-02-24	
6-RA-103-10	10.97	4.57	2001-03-02	10.78	10.27	0.075	0.102	>50	2016-02-24	

Line 3-RV-101 | Regenerator overhead | A106 Gr.B | t_nom 7.62 mm | t-min 3.56 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
3-RV-101-01	7.62	3.56	2001-03-02	7.26	6.98	0.061	0.056	>50	2011-02-24	
3-RV-101-02	7.62	3.56	2001-03-02	7.31	6.93	0.064	0.076	44.2	2011-02-24	
3-RV-101-03	7.62	3.56	2001-03-02	7.15	6.57	0.095	0.116	25.9	2011-02-24	
3-RV-101-04	7.62	3.56	2001-03-02	7.18	6.65	0.094	0.106	29.1	2011-02-24	

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
3-RV-101-05	7.62	3.56	2001-03-02	7.25	7.01	0.066	0.048	>50	2011-02-24	
3-RV-101-06	7.62	3.56	2001-03-02	7.20	6.74	0.085	0.092	34.4	2011-02-24	

Line 2-RV-102 | Regenerator overhead | A106 Gr.B | t_nom 5.54 mm | t-min 2.79 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
2-RV-102-01	5.54	2.79	2001-03-02	5.29	4.85	0.068	0.088	23.3	2011-02-24	
2-RV-102-02	5.54	2.79	2001-03-02	5.12	4.84	0.075	0.056	27.2	2011-02-24	
2-RV-102-03	5.54	2.79	2001-03-02	5.24	5.14	0.034	0.020	>50	2011-02-24	
2-RV-102-04	5.54	2.79	2001-03-02	5.33	5.07	0.051	0.052	43.7	2011-02-24	

Line 3-RF-101 | Reflux | A312 TP316 | t_nom 5.49 mm | t-min 2.41 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
3-RF-101-01	5.49	2.41	1996-03-08	5.48	5.48	0.000	0.000	>50	2016-02-24	
3-RF-101-02	5.49	2.41	1996-03-08	5.45	5.37	0.008	0.008	>50	2016-02-24	
3-RF-101-03	5.49	2.41	1996-03-08	5.45	5.45	0.000	0.000	>50	2016-02-24	
3-RF-101-04	5.49	2.41	1996-03-08	5.46	5.33	0.013	0.013	>50	2016-02-24	
3-RF-101-05	5.49	2.41	1996-03-08	5.45	5.40	0.005	0.005	>50	2016-02-24	
3-RF-101-06	5.49	2.41	1996-03-08	5.52	5.40	0.012	0.012	>50	2016-02-24	
3-RF-101-07	5.49	2.41	1996-03-08	5.42	5.35	0.007	0.007	>50	2016-02-24	

Line 2-RF-102 | Reflux | A312 TP316 | t_nom 3.91 mm | t-min 2.16 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
2-RF-102-01	3.91	2.16	1996-03-08	3.92	3.85	0.007	0.007	>50	2016-02-24	
2-RF-102-02	3.91	2.16	1996-03-08	3.88	3.88	0.000	0.000	>50	2016-02-24	
2-RF-102-03	3.91	2.16	1996-03-08	3.93	3.80	0.013	0.013	>50	2016-02-24	
2-RF-102-04	3.91	2.16	1996-03-08	3.87	3.81	0.006	0.006	>50	2016-02-24	
2-RF-102-07	3.91	2.16	1996-03-08	3.96	3.85	0.011	0.011	>50	2016-02-24	

Line 4-LA-104 | L/R exchanger, lean side | A106 Gr.B | t_nom 6.02 mm | t-min 3.18 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-LA-104-01	6.02	3.18	1996-03-08	6.07	5.75	0.032	0.032	>50	2016-02-24	
4-LA-104-02	6.02	3.18	1996-03-08	6.03	5.56	0.047	0.047	>50	2016-02-24	
4-LA-104-03	6.02	3.18	1996-03-08	5.96	5.74	0.022	0.022	>50	2016-02-24	
4-LA-104-04	6.02	3.18	1996-03-08	6.06	5.86	0.020	0.020	>50	2016-02-24	
4-LA-104-05	6.02	3.18	1996-03-08	6.04	5.51	0.053	0.053	43.8	2016-02-24	
4-LA-104-06	6.02	3.18	1996-03-08	6.10	5.83	0.027	0.027	>50	2016-02-24	
4-LA-104-07	6.02	3.18	1996-03-08	6.01	5.62	0.039	0.039	>50	2016-02-24	
4-LA-104-08	6.02	3.18	1996-03-08	5.94	5.50	0.044	0.044	>50	2016-02-24	

Line 4-RA-104 | L/R exchanger, rich side | A106 Gr.B | t_nom 8.56 mm | t-min 3.81 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-RA-104-01	8.56	3.81	2001-03-02	8.40	8.16	0.035	0.048	>50	2016-02-24	
4-RA-104-02	8.56	3.81	2001-03-02	8.41	8.23	0.032	0.036	>50	2016-02-24	
4-RA-104-03	8.56	3.81	2001-03-02	8.46	8.30	0.024	0.032	>50	2016-02-24	
4-RA-104-04	8.56	3.81	2001-03-02	8.35	8.21	0.038	0.028	>50	2016-02-24	
4-RA-104-05	8.56	3.81	2001-03-02	8.29	8.14	0.046	0.030	>50	2016-02-24	
4-RA-104-06	8.56	3.81	2001-03-02	8.39	8.09	0.050	0.060	>50	2016-02-24	
4-RA-104-07	8.56	3.81	2001-03-02	8.29	7.97	0.062	0.064	>50	2016-02-24	

Line 2-ST-101 | Reboiler steam | A106 Gr.B | t_nom 3.91 mm | t-min 2.29 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
2-ST-101-01	3.91	2.29	1996-03-08	3.93	3.64	0.029	0.029	46.4	2016-02-24	
2-ST-101-02	3.91	2.29	1996-03-08	3.90	3.67	0.023	0.023	>50	2016-02-24	
2-ST-101-03	3.91	2.29	1996-03-08	3.94	3.82	0.012	0.012	>50	2016-02-24	
2-ST-101-04	3.91	2.29	1996-03-08	3.82	3.77	0.005	0.005	>50	2016-02-24	
2-ST-101-05	3.91	2.29	1996-03-08	3.91	3.72	0.019	0.019	>50	2016-02-24	

Line 3-CW-101 | Amine cooler CW | A106 Gr.B | t_nom 5.49 mm | t-min 2.79 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
3-CW-101-01	5.49	2.79	1996-03-08	5.42	5.13	0.029	0.029	>50	2016-02-24	
3-CW-101-02	5.49	2.79	1996-03-08	5.41	5.20	0.021	0.021	>50	2016-02-24	
3-CW-101-03	5.49	2.79	1996-03-08	5.53	5.08	0.045	0.045	>50	2016-02-24	
3-CW-101-04	5.49	2.79	1996-03-08	5.46	5.38	0.008	0.008	>50	2016-02-24	
3-CW-101-05	5.49	2.79	1996-03-08	5.48	5.33	0.015	0.015	>50	2016-02-24	

Line 3-CW-102 | Amine cooler CW | A106 Gr.B | t_nom 5.49 mm | t-min 2.79 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
3-CW-102-01	5.49	2.79	1996-03-08	5.50	5.20	0.030	0.030	>50	2016-02-24	
3-CW-102-02	5.49	2.79	1996-03-08	5.51	5.02	0.049	0.049	45.4	2016-02-24	
3-CW-102-03	5.49	2.79	1996-03-08	5.53	5.07	0.046	0.046	49.4	2016-02-24	
3-CW-102-04	5.49	2.79	1996-03-08	5.51	5.03	0.048	0.048	46.5	2016-02-24	

Sign-off	Name	Function	Date	Signature
Prepared	Kevin Doucette	lead UT technician, SNT-TC-1A UT Level II	2006-02-24	_____
Reviewed	Anil Rao	Level III, SNT-TC-1A UT/RT Level III	2006-02-24	_____