Larkhall NDE Services Inc.

Inspection Report

Site: Hamilton Plant

No.	Status	Date
LNDE-RPT-20220906-033-R0	Issued	2022-09-16

UT Thickness Survey - ATU-100 Sour Gas, Regenerator Overhead, Rich Amine

Scope and Objectives

This report details the 3-year RBI survey conducted at the Hamilton Plant for the ATU-100. The scope of work was limited to Class 1 sour gas, regenerator overhead, and rich amine systems as defined by QSCP-IP-ATU100 Rev 3. The primary objective was to perform ultrasonic thickness measurements to assess the current condition of the piping and ensure compliance with API 570 and ASME B31.3 requirements.

The inspection targeted specific circuits including sour gas inlet lines 6-SG-101 and 6-SG-102, regenerator overhead lines 3-RV-101 and 2-RV-102, and rich amine lines 4-RA-101, 4-RA-102, 6-RA-103, and 4-RA-104. Per the risk-based intervals established in QSCP-IP-ATU100 Rev 3, the reflux lines were excluded from this scope as they are subject to a 6-year RBI interval.

Personnel and Methodology

The survey was performed by Marcus Chen, acting as the lead UT technician. All ultrasonic thickness measurements were executed in accordance with QSCP-NDT-001 Rev 2, which incorporates specific requirements for the CUI program, including insulation removal and inspection-port management. The methodology followed ASTM E797 to ensure high-resolution data acquisition across the A106 Gr.B carbon steel components.

Equipment calibration was verified using LNDE-CAL-2022-0791 for the Olympus 38DL PLUS 2847193 gauge. All personnel qualifications were maintained under ASNT SNT-TC-1A. David Park provided the technical review and quality oversight for the data collected during this mobilization, ensuring that all readings were compared against the baseline data established in LNDE-RPT-20191001-027-R0.

Inspection Findings and CML Status

Thickness data was collected for 150 CMLs across the identified lines. For the sour gas inlet lines 6-SG-101 and 6-SG-102, readings remained well above the t-min of 3.56 mm. Similarly, the regenerator overhead lines 3-RV-101 and 2-RV-102 showed no significant wall loss, maintaining thicknesses above their respective retirement limits of 3.56 mm and 2.79 mm. The rich amine header 6-RA-103 and exchanger line 4-RA-104 also showed stability relative to the 2019 survey.

Access limitations were encountered during the survey. Specifically, elevated CMLs 4-RA-101-06 and 6-RA-103-11 were recorded as inaccessible due to the absence of required scaffolding. In accordance with the site inspection strategy, these specific locations have been carried forward to the 2024 survey cycle. All other accessible points on 4-RA-101, 4-RA-102, and 6-RA-103 were successfully measured.

Integrity Assessment

Corrosion rates were calculated by Marcus Chen using the short-term rate over the 3-year interval since LNDE-RPT-20191001-027-R0. No readings were found to be below the t-min thresholds defined for the A106 Gr.B piping, which range from 2.79 mm to 4.57 mm depending on the line class and design pressure. Consequently, no NCRs were issued during this inspection period.

The remaining life for all inspected circuits exceeds the current 3-year RBI interval. David Park has confirmed that the next thickness reading for these Class 1 systems shall be scheduled within the 5-year maximum for Class 1 piping as per site rules, or as dictated by the 3-year RBI cycle defined in QSCP-IP-ATU100 Rev 3. The CUI program requirements for profile radiography and insulation windows remain active for the next 5-year cycle.

Thickness readings, measured 2022-09-16

Line 6-SG-101 | Sour gas inlet | A106 Gr.B | t_nom 7.11 mm | t-min 3.56 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-SG-101-01	7.11	3.56	2019-10-18	5.93	5.82	0.049	0.053	42.6	2025-09-16	
6-SG-101-02	7.11	3.56	2019-10-18	5.51	5.42	0.061	0.052	30.3	2025-09-16	
6-SG-101-03	7.11	3.56	2019-10-18	5.56	5.29	0.067	0.088	19.7	2025-09-16	
6-SG-101-04	7.11	3.56	2019-10-18	5.34	5.19	0.072	0.059	22.8	2025-09-16	
6-SG-101-05	7.11	3.56	2019-10-18	5.04	4.72	0.091	0.100	11.6	2025-09-16	

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-SG-101-06	7.11	3.56	2019-10-18	5.56	5.55	0.057	0.050	34.7	2025-09-16	
6-SG-101-07	7.11	3.56	2019-10-18	6.24	6.16	0.027	0.027	>50	2025-09-16	
6-SG-101-08	7.11	3.56	2019-10-18	5.77	5.57	0.066	0.065	30.6	2025-09-16	

Line 6-SG-102 | Sour gas inlet | A106 Gr.B | t_nom 7.11 mm | t-min 3.56 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-SG-102-01	7.11	3.56	2019-10-18	5.05	4.77	0.089	0.099	12.3	2025-09-16	
6-SG-102-02	7.11	3.56	2019-10-18	5.10	4.64	0.093	0.120	9.0	2025-09-16	
6-SG-102-03	7.11	3.56	2019-10-18	4.92	4.69	0.089	0.080	12.8	2025-09-16	
6-SG-102-04	7.11	3.56	2019-10-18	4.90	4.62	0.089	0.085	11.9	2025-09-16	
6-SG-102-05	7.11	3.56	2019-10-18	6.07	5.96	0.044	0.035	>50	2025-09-16	
6-SG-102-06	7.11	3.56	2019-10-18	6.03	5.79	0.054	0.041	41.6	2025-09-16	

Line 4-RA-101 | Rich amine | A106 Gr.B | t_nom 8.56 mm | t-min 3.81 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-RA-101-01	8.56	3.81	2019-10-18	7.29	6.83	0.064	0.152	19.9	2025-09-16	
4-RA-101-02	8.56	3.81	2019-10-18	7.39	6.79	0.066	0.174	17.1	2025-09-16	
4-RA-101-03	8.56	3.81	2019-10-18	6.64	5.98	0.099	0.253	8.6	2025-09-16	
4-RA-101-04	8.56	3.81	2019-10-18	7.54	7.21	0.054	0.120	28.4	2025-09-16	
4-RA-101-05	8.56	3.81	2019-10-18	7.18	6.73	0.071	0.165	17.7	2025-09-16	
4-RA-101-06	8.56	3.81	2019-10-18	6.94	—	—	—	—	—	inaccessible – no reading
4-RA-101-07	8.56	3.81	2019-10-18	7.68	7.50	0.041	0.097	38.0	2025-09-16	
4-RA-101-08	8.56	3.81	2019-10-18	6.45	5.55	0.118	0.267	6.5	2025-09-16	
4-RA-101-09	8.56	3.81	2019-10-18	7.68	7.37	0.045	0.115	30.9	2025-09-16	
4-RA-101-10	8.56	3.81	2019-10-18	7.55	7.19	0.056	0.126	26.8	2025-09-16	
4-RA-101-11	8.56	3.81	2019-10-18	6.66	6.07	0.098	0.232	9.7	2025-09-16	
4-RA-101-12	8.56	3.81	2019-10-18	7.03	6.41	0.213	0.213	12.2	2025-09-16	

Line 4-RA-102 | Rich amine | A106 Gr.B | t_nom 8.56 mm | t-min 3.81 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-RA-102-01	8.56	3.81	2019-10-18	7.58	7.42	0.042	0.091	39.7	2025-09-16	
4-RA-102-02	8.56	3.81	2019-10-18	6.96	6.43	0.081	0.184	14.3	2025-09-16	
4-RA-102-03	8.56	3.81	2019-10-18	7.05	6.56	0.075	0.150	18.3	2025-09-16	
4-RA-102-04	8.56	3.81	2019-10-18	7.04	6.64	0.072	0.164	17.3	2025-09-16	
4-RA-102-05	8.56	3.81	2019-10-18	7.06	6.56	0.075	0.168	16.3	2025-09-16	
4-RA-102-06	8.56	3.81	2019-10-18	7.15	6.65	0.070	0.164	17.3	2025-09-16	
4-RA-102-07	8.56	3.81	2019-10-18	7.30	6.85	0.065	0.141	21.6	2025-09-16	
4-RA-102-08	8.56	3.81	2019-10-18	6.40	5.86	0.099	0.226	9.1	2025-09-16	
4-RA-102-09	8.56	3.81	2019-10-18	6.78	6.42	0.080	0.170	15.4	2025-09-16	
4-RA-102-10	8.56	3.81	2019-10-18	7.36	6.86	0.172	0.172	17.8	2025-09-16	
4-RA-102-11	8.56	3.81	2019-10-18	7.72	7.33	0.074	0.096	36.8	2025-09-16	

Line 6-RA-103 | Rich amine header | A106 Gr.B | t_nom 10.97 mm | t-min 4.57 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-RA-103-01	10.97	4.57	2019-10-18	9.83	9.55	0.055	0.112	44.4	2025-09-16	
6-RA-103-02	10.97	4.57	2019-10-18	8.61	7.97	0.118	0.261	13.0	2025-09-16	
6-RA-103-03	10.97	4.57	2019-10-18	9.49	8.95	0.077	0.168	26.0	2025-09-16	
6-RA-103-04	10.97	4.57	2019-10-18	8.22	7.30	0.139	0.305	9.0	2025-09-16	
6-RA-103-05	10.97	4.57	2019-10-18	8.33	7.43	0.133	0.311	9.2	2025-09-16	
6-RA-103-06	10.97	4.57	2019-10-18	9.79	9.45	0.059	0.132	37.0	2025-09-16	

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-RA-103-07	10.97	4.57	2019-10-18	9.59	9.15	0.069	0.159	28.8	2025-09-16	
6-RA-103-08	10.97	4.57	2019-10-18	9.73	9.29	0.063	0.158	29.9	2025-09-16	
6-RA-103-09	10.97	4.57	2019-10-18	9.78	9.43	0.060	0.137	35.6	2025-09-16	
6-RA-103-10	10.97	4.57	2019-10-18	8.37	7.68	0.126	0.275	11.3	2025-09-16	
6-RA-103-11	10.97	4.57	2019-10-18	8.91	—	—	—	—	—	inaccessible – no reading
6-RA-103-12	10.97	4.57	2019-10-18	9.52	9.11	0.141	0.141	32.3	2025-09-16	
6-RA-103-13	10.97	4.57	2019-10-18	9.55	9.13	0.114	0.155	29.5	2025-09-16	
6-RA-103-14	10.97	4.57	2019-10-18	8.26	7.34	0.316	0.316	8.8	2025-09-16	

Line 3-RV-101 | Regenerator overhead | A106 Gr.B | t_nom 7.62 mm | t-min 3.56 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
3-RV-101-01	7.62	3.56	2019-10-18	6.05	5.92	0.063	0.064	37.0	2025-09-16	
3-RV-101-02	7.62	3.56	2019-10-18	5.97	5.81	0.066	0.076	29.7	2025-09-16	
3-RV-101-03	7.62	3.56	2019-10-18	5.24	4.98	0.096	0.099	14.4	2025-09-16	
3-RV-101-04	7.62	3.56	2019-10-18	5.58	5.39	0.083	0.074	22.1	2025-09-16	
3-RV-101-05	7.62	3.56	2019-10-18	6.11	5.91	0.066	0.068	34.4	2025-09-16	
3-RV-101-06	7.62	3.56	2019-10-18	5.55	5.39	0.083	0.086	21.2	2025-09-16	
3-RV-101-07	7.62	3.56	2019-10-18	5.07	4.80	0.117	0.112	10.6	2025-09-16	
3-RV-101-08	7.62	3.56	2019-10-18	5.86	5.81	0.075	0.076	29.7	2025-09-16	

Line 2-RV-102 | Regenerator overhead | A106 Gr.B | t_nom 5.54 mm | t-min 2.79 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
2-RV-102-01	5.54	2.79	2019-10-18	4.16	3.91	0.061	0.067	16.8	2025-09-16	
2-RV-102-02	5.54	2.79	2019-10-18	3.86	3.64	0.074	0.056	11.6	2025-09-16	
2-RV-102-03	5.54	2.79	2019-10-18	4.37	4.34	0.043	0.046	34.1	2025-09-16	
2-RV-102-04	5.54	2.79	2019-10-18	4.59	4.47	0.042	0.039	40.1	2025-09-16	
2-RV-102-05	5.54	2.79	2019-10-18	4.78	4.59	0.037	0.058	31.2	2025-09-16	
2-RV-102-06	5.54	2.79	2019-10-18	4.27	4.05	0.064	0.033	19.6	2025-09-16	

Line 4-RA-104 | L/R exchanger, rich side | A106 Gr.B | t_nom 8.56 mm | t-min 3.81 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-RA-104-01	8.56	3.81	2019-10-18	7.15	6.61	0.072	0.167	16.8	2025-09-16	
4-RA-104-02	8.56	3.81	2019-10-18	7.31	7.04	0.057	0.123	26.3	2025-09-16	
4-RA-104-03	8.56	3.81	2019-10-18	7.94	7.70	0.074	0.088	44.2	2025-09-16	
4-RA-104-04	8.56	3.81	2019-10-18	7.64	7.31	0.101	0.132	26.5	2025-09-16	
4-RA-104-05	8.56	3.81	2019-10-18	7.57	7.12	0.109	0.158	21.0	2025-09-16	
4-RA-104-06	8.56	3.81	2019-10-18	7.13	6.70	0.071	0.138	20.9	2025-09-16	
4-RA-104-07	8.56	3.81	2019-10-18	6.67	6.04	0.096	0.194	11.5	2025-09-16	
4-RA-104-08	8.56	3.81	2019-10-18	7.46	7.09	0.094	0.109	30.0	2025-09-16	

Sign-off	Name	Function	Date	Signature
Prepared	Marcus Chen	lead UT technician, SNT-TC-1A UT/MT/PT Level II; CAN/CGSB-48.9712 UT Level II	2022-09-16	_____
Reviewed	David Park	Level III / Quality Manager, SNT-TC-1A UT Level III	2022-09-16	_____