No.	Status	Date
LNDE-RPT-20241025-031-R0	DRAFT – issued for review	2024-11-14

UT Thickness Survey - ATU-100 Five-Year (Draft)

Scope and Responsibilities

This report details the five-year ultrasonic thickness survey conducted at the Hamilton Plant for the ATU-100 unit. The inspection was performed in response to QSCP-RFQ-2024-089 to assess the current wall thickness of 150 Condition Monitoring Locations across 18 process lines. Marcus Chen served as the lead UT technician, responsible for data acquisition and field measurements, while David Park provided technical oversight and quality management for the survey results.

The survey was executed in accordance with QSCP-NDT-001 Rev 3, which aligns with the requirements of QSCP-CIS-001 Rev 1. This procedure mandates digital export of readings and specific photo documentation for any measurements falling below the alert level. The inspection scope and CML rationalization were governed by QSCP-IP-ATU100 Rev 3, which sets Risk-Based Inspection intervals at 3 years for Class 1 sour gas, regenerator overhead, and rich amine services, and 6 years for all other lines.

Standards and Calibration

Field measurements were performed following the technical requirements of API 570 and ASTM E797. The design and construction standards for the piping systems are referenced under ASME B31.3. All personnel involved in the NDE activities were certified in accordance with ASNT SNT-TC-1A to ensure technical competency and adherence to industry best practices for ultrasonic testing.

Instrumentation used during the survey included Olympus 38DL PLUS 2847193 and Olympus 38DL PLUS 2901456, both calibrated as per LNDE-CAL-2024-0847 and LNDE-CAL-2024-0848. The carbon steel step block LNDE-CS-001 was utilized for field verification, having been re-certified under LNDE-CAL-2024-0102. For the A312 TP316 stainless steel lines, the gauges were adjusted to the appropriate material velocity setting.

Inspection Methodology and Data Comparison

The current thickness data was compared against the previous results documented in LNDE-RPT-20191001-027-R0 to determine corrosion rates. Per site rules, the corrosion rate is calculated as the larger of the long-term rate since the first reading and the short-term rate over the latest pair of readings at least 3 years apart. Remaining life is determined by the formula (t - t-min) / rate, where t-min is the retirement thickness defined in the line facts.

The survey covered carbon steel lines including 6-SG-101, 6-SG-102, 8-TG-101, 4-LA-101, 4-LA-102, 6-LA-103, 4-RA-102, 6-RA-103, 3-RV-101, 2-RV-102, 4-LA-104, 4-RA-104, 2-ST-101, 3-CW-101, and 3-CW-102. Stainless steel lines 3-RF-101 and 2-RF-102 were also inspected. Retirement thicknesses range from 2.16 mm for reflux lines to 4.57 mm for the rich amine header.

Summary of Findings and Non-Conformances

Several CMLs were found to have reached their retirement thickness, resulting in expired remaining life. Specifically, on line 2-RF-102, CMLs 04, 05, 06, and 07 recorded thicknesses of 1.94 mm, 1.92 mm, 1.92 mm, and 1.86 mm respectively, all of which are below the t-min of 2.16 mm. Additionally, CML 4-RA-101-06 on line 4-RA-101 recorded a thickness of 3.59 mm, which is below the t-min of 3.81 mm.

In accordance with site rules, these readings below t-min have been raised as Non-Conformance Reports. The remaining life for these specific locations is considered expired, and immediate engineering assessment is required. All other lines, including the reboiler steam line 2-ST-101 and cooling water lines 3-CW-101 and 3-CW-102, currently maintain thicknesses above their respective retirement limits.

Thickness readings, measured 2024-11-04

Line 6-SG-101 | Sour gas inlet | A106 Gr.B | t_nom 7.11 mm | t-min 3.56 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-SG-101-01	7.11	3.56	2022-09-16	5.82	5.64	0.052	0.057	36.2	2027-11-04	
6-SG-101-02	7.11	3.56	2022-09-16	5.42	5.12	0.067	0.077	20.2	2027-11-04	
6-SG-101-03	7.11	3.56	2022-09-16	5.29	5.25	0.064	0.061	26.5	2027-11-04	
6-SG-101-04	7.11	3.56	2022-09-16	5.19	4.98	0.074	0.071	19.3	2027-11-04	

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-SG-101-05	7.11	3.56	2022-09-16	4.72	4.65	0.087	0.077	12.5	2027-11-04	
6-SG-101-06	7.11	3.56	2022-09-16	5.55	5.39	0.059	0.034	31.2	2027-11-04	
6-SG-101-07	7.11	3.56	2022-09-16	6.16	6.04	0.040	0.040	>50	2027-11-04	
6-SG-101-08	7.11	3.56	2022-09-16	5.57	5.54	0.058	0.046	34.4	2027-11-04	

Line 6-SG-102 | Sour gas inlet | A106 Gr.B | t_nom 7.11 mm | t-min 3.56 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-SG-102-01	7.11	3.56	2022-09-16	4.77	4.62	0.088	0.085	12.1	2027-11-04	
6-SG-102-02	7.11	3.56	2022-09-16	4.64	4.59	0.088	0.101	10.2	2027-11-04	
6-SG-102-03	7.11	3.56	2022-09-16	4.69	4.45	0.090	0.093	9.6	2027-11-04	gauge photo attached
6-SG-102-04	7.11	3.56	2022-09-16	4.62	4.39	0.091	0.101	8.2	2027-11-04	
6-SG-102-05	7.11	3.56	2022-09-16	5.96	5.89	0.043	0.036	>50	2027-11-04	
6-SG-102-06	7.11	3.56	2022-09-16	5.79	5.82	0.043	0.042	>50	2027-11-04	

Line 8-TG-101 | Treated gas | A106 Gr.B | t_nom 8.18 mm | t-min 4.06 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
8-TG-101-01	8.18	4.06	2019-10-18	7.63	7.57	0.022	0.012	>50	2030-11-04	
8-TG-101-02	8.18	4.06	2019-10-18	7.33	7.21	0.035	0.024	>50	2030-11-04	
8-TG-101-03	8.18	4.06	2019-10-18	7.37	7.27	0.033	0.020	>50	2030-11-04	
8-TG-101-04	8.18	4.06	2019-10-18	7.38	7.29	0.028	0.018	>50	2030-11-04	
8-TG-101-05	8.18	4.06	2019-10-18	7.57	7.54	0.024	0.006	>50	2030-11-04	
8-TG-101-06	8.18	4.06	2019-10-18	7.75	7.61	0.028	0.028	>50	2030-11-04	
8-TG-101-07	8.18	4.06	2019-10-18	7.17	6.98	0.047	0.038	>50	2030-11-04	

Line 4-LA-101 | Lean amine supply | A106 Gr.B | t_nom 6.02 mm | t-min 3.18 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-LA-101-01	6.02	3.18	2019-10-18	4.70	4.46	0.053	0.048	24.0	2030-11-04	
4-LA-101-02	6.02	3.18	2019-10-18	5.26	5.23	0.027	0.006	>50	2030-11-04	
4-LA-101-03	6.02	3.18	2019-10-18	5.38	5.19	0.027	0.038	>50	2030-11-04	
4-LA-101-04	6.02	3.18	2019-10-18	5.29	5.13	0.033	0.032	>50	2030-11-04	
4-LA-101-05	6.02	3.18	2019-10-18	5.38	5.25	0.027	0.026	>50	2030-11-04	
4-LA-101-06	6.02	3.18	2019-10-18	5.22	4.91	0.040	0.061	28.2	2030-11-04	
4-LA-101-07	6.02	3.18	2019-10-18	4.86	4.49	0.052	0.073	17.9	2030-11-04	
4-LA-101-08	6.02	3.18	2019-10-18	5.04	4.70	0.067	0.067	22.6	2030-11-04	
4-LA-101-09	6.02	3.18	2019-10-18	4.86	4.57	0.049	0.057	24.2	2030-11-04	

Line 4-LA-102 | Lean amine supply | A106 Gr.B | t_nom 6.02 mm | t-min 3.18 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-LA-102-01	6.02	3.18	2019-10-18	5.09	5.03	0.035	0.012	>50	2030-11-04	
4-LA-102-02	6.02	3.18	2019-10-18	5.15	5.08	0.035	0.014	>50	2030-11-04	
4-LA-102-03	6.02	3.18	2019-10-18	5.15	4.93	0.040	0.044	40.2	2030-11-04	
4-LA-102-04	6.02	3.18	2019-10-18	4.65	4.40	0.055	0.050	22.0	2030-11-04	
4-LA-102-05	6.02	3.18	2019-10-18	5.23	5.06	0.033	0.034	>50	2030-11-04	
4-LA-102-06	6.02	3.18	2019-10-18	5.52	5.42	0.020	0.020	>50	2030-11-04	
4-LA-102-07	6.02	3.18	2019-10-18	5.32	5.13	0.030	0.038	>50	2030-11-04	
4-LA-102-08	6.02	3.18	2019-10-18	5.55	5.38	0.037	0.034	>50	2030-11-04	

Line 6-LA-103 | Lean amine header | A106 Gr.B | t_nom 7.11 mm | t-min 3.56 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-LA-103-01	7.11	3.56	2019-10-18	6.40	6.27	0.026	0.026	>50	2030-11-04	
6-LA-103-02	7.11	3.56	2019-10-18	6.49	6.28	0.032	0.042	>50	2030-11-04	
6-LA-103-03	7.11	3.56	2019-10-18	6.23	5.95	0.039	0.055	43.1	2030-11-04	
6-LA-103-04	7.11	3.56	2019-10-18	5.85	5.64	0.053	0.042	39.0	2030-11-04	
6-LA-103-05	7.11	3.56	2019-10-18	5.81	5.43	0.061	0.075	24.8	2030-11-04	
6-LA-103-06	7.11	3.56	2019-10-18	5.46	5.10	0.072	0.071	21.4	2030-11-04	
6-LA-103-07	7.11	3.56	2019-10-18	5.93	5.73	0.051	0.040	42.9	2030-11-04	
6-LA-103-08	7.11	3.56	2019-10-18	6.19	—	—	—	—	—	inaccessible – no reading
6-LA-103-09	7.11	3.56	2019-10-18	6.16	5.92	0.048	0.048	49.6	2030-11-04	
6-LA-103-10	7.11	3.56	2019-10-18	6.00	5.74	0.064	0.051	34.0	2030-11-04	

Line 4-RA-101 | Rich amine | A106 Gr.B | t_nom 8.56 mm | t-min 3.81 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-RA-101-01	8.56	3.81	2022-09-16	6.83	6.50	0.070	0.156	17.2	2027-11-04	
4-RA-101-02	8.56	3.81	2022-09-16	6.79	6.46	0.073	0.184	14.4	2027-11-04	
4-RA-101-03	8.56	3.81	2022-09-16	5.98	5.52	0.108	0.222	7.7	2027-11-04	gauge photo attached
4-RA-101-04	8.56	3.81	2022-09-16	7.21	6.90	0.060	0.127	24.4	2027-11-04	
4-RA-101-05	8.56	3.81	2022-09-16	6.73	6.37	0.078	0.160	16.0	2027-11-04	
4-RA-101-06	8.56	3.81	2019-10-18	6.94	3.59	0.427	0.664	expired	immediate	< t-min; gauge photo attached
4-RA-101-07	8.56	3.81	2022-09-16	7.50	7.21	0.048	0.093	36.5	2027-11-04	
4-RA-101-08	8.56	3.81	2022-09-16	5.55	5.06	0.126	0.275	4.5	2027-02-10	gauge photo attached
4-RA-101-09	8.56	3.81	2022-09-16	7.37	7.17	0.049	0.101	33.3	2027-11-04	
4-RA-101-10	8.56	3.81	2022-09-16	7.19	6.91	0.061	0.127	24.5	2027-11-04	
4-RA-101-11	8.56	3.81	2022-09-16	6.07	5.53	0.110	0.224	7.7	2027-11-04	gauge photo attached
4-RA-101-12	8.56	3.81	2022-09-16	6.41	6.10	0.184	0.184	12.4	2027-11-04	

Line 4-RA-102 | Rich amine | A106 Gr.B | t_nom 8.56 mm | t-min 3.81 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-RA-102-01	8.56	3.81	2022-09-16	7.42	7.33	0.042	0.050	>50	2027-11-04	
4-RA-102-02	8.56	3.81	2022-09-16	6.43	5.99	0.090	0.192	11.3	2027-11-04	
4-RA-102-03	8.56	3.81	2022-09-16	6.56	6.24	0.081	0.160	15.1	2027-11-04	
4-RA-102-04	8.56	3.81	2022-09-16	6.64	6.38	0.075	0.131	19.7	2027-11-04	
4-RA-102-05	8.56	3.81	2022-09-16	6.56	6.23	0.081	0.164	14.7	2027-11-04	
4-RA-102-05	8.56	3.81	2022-09-16	6.56	6.23	0.081	0.164	14.7	2027-11-04	
4-RA-102-06	8.56	3.81	2022-09-16	6.65	6.35	0.075	0.158	16.0	2027-11-04	
4-RA-102-07	8.56	3.81	2022-09-16	6.85	6.53	0.072	0.153	17.8	2027-11-04	
4-RA-102-08	8.56	3.81	2022-09-16	5.86	5.26	0.113	0.226	6.4	2027-11-04	gauge photo attached
4-RA-102-09	8.56	3.81	2022-09-16	6.42	6.04	0.088	0.147	15.2	2027-11-04	
4-RA-102-10	8.56	3.81	2022-09-16	6.86	6.56	0.158	0.158	17.4	2027-11-04	
4-RA-102-11	8.56	3.81	2022-09-16	7.33	7.19	0.073	0.105	32.2	2027-11-04	

Line 6-RA-103 | Rich amine header | A106 Gr.B | t_nom 10.97 mm | t-min 4.57 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-RA-103-01	10.97	4.57	2022-09-16	9.55	9.28	0.060	0.109	43.2	2027-11-04	
6-RA-103-02	10.97	4.57	2022-09-16	7.97	7.33	0.131	0.254	10.9	2027-11-04	
6-RA-103-03	10.97	4.57	2022-09-16	8.95	8.44	0.089	0.208	18.6	2027-11-04	
6-RA-103-04	10.97	4.57	2022-09-16	7.30	6.60	0.153	0.321	6.3	2027-11-04	gauge photo attached
6-RA-103-05	10.97	4.57	2022-09-16	7.43	6.91	0.141	0.281	8.3	2027-11-04	gauge photo attached
6-RA-103-06	10.97	4.57	2022-09-16	9.45	9.16	0.065	0.125	36.8	2027-11-04	

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
6-RA-103-07	10.97	4.57	2022-09-16	9.15	8.89	0.073	0.139	31.2	2027-11-04	
6-RA-103-08	10.97	4.57	2022-09-16	9.29	9.07	0.066	0.131	34.4	2027-11-04	
6-RA-103-09	10.97	4.57	2022-09-16	9.43	9.10	0.067	0.135	33.6	2027-11-04	
6-RA-103-10	10.97	4.57	2022-09-16	7.68	7.00	0.140	0.271	9.0	2027-11-04	gauge photo attached
6-RA-103-11	10.97	4.57	2019-10-18	8.91	5.92	0.413	0.592	2.3	2025-12-25	gauge photo attached
6-RA-103-12	10.97	4.57	2022-09-16	9.11	8.74	0.154	0.154	27.0	2027-11-04	
6-RA-103-13	10.97	4.57	2022-09-16	9.13	8.92	0.112	0.125	34.9	2027-11-04	
6-RA-103-14	10.97	4.57	2022-09-16	7.34	6.52	0.345	0.345	5.7	2027-09-02	gauge photo attached

Line 3-RV-101 | Regenerator overhead | A106 Gr.B | t_nom 7.62 mm | t-min 3.56 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
3-RV-101-01	7.62	3.56	2022-09-16	5.92	5.74	0.065	0.061	33.8	2027-11-04	
3-RV-101-02	7.62	3.56	2022-09-16	5.81	5.70	0.065	0.053	32.8	2027-11-04	
3-RV-101-03	7.62	3.56	2022-09-16	4.98	4.72	0.098	0.103	11.3	2027-11-04	
3-RV-101-04	7.62	3.56	2022-09-16	5.39	5.18	0.084	0.079	19.3	2027-11-04	
3-RV-101-05	7.62	3.56	2022-09-16	5.91	5.84	0.064	0.053	35.7	2027-11-04	
3-RV-101-06	7.62	3.56	2022-09-16	5.39	5.22	0.083	0.065	20.1	2027-11-04	
3-RV-101-07	7.62	3.56	2022-09-16	4.80	4.63	0.111	0.087	9.6	2027-11-04	gauge photo attached
3-RV-101-08	7.62	3.56	2022-09-16	5.81	5.64	0.076	0.044	27.5	2027-11-04	

Line 2-RV-102 | Regenerator overhead | A106 Gr.B | t_nom 5.54 mm | t-min 2.79 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
2-RV-102-01	5.54	2.79	2022-09-16	3.91	3.76	0.062	0.079	12.2	2027-11-04	
2-RV-102-02	5.54	2.79	2022-09-16	3.64	3.49	0.073	0.073	9.6	2027-11-04	gauge photo attached
2-RV-102-03	5.54	2.79	2022-09-16	4.34	4.23	0.044	0.028	33.0	2027-11-04	
2-RV-102-04	5.54	2.79	2022-09-16	4.47	4.39	0.042	0.040	38.5	2027-11-04	
2-RV-102-05	5.54	2.79	2022-09-16	4.59	4.57	0.033	0.042	42.8	2027-11-04	
2-RV-102-06	5.54	2.79	2022-09-16	4.05	3.94	0.062	0.065	17.6	2027-11-04	

Line 3-RF-101 | Reflux | A312 TP316 | t_nom 5.49 mm | t-min 2.41 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
3-RF-101-01	5.49	2.41	2019-10-18	5.40	5.15	0.012	0.050	>50	2030-11-04	
3-RF-101-02	5.49	2.41	2019-10-18	5.38	5.24	0.007	0.028	>50	2030-11-04	
3-RF-101-03	5.49	2.41	2019-10-18	5.35	5.35	0.003	0.000	>50	2030-11-04	
3-RF-101-04	5.49	2.41	2019-10-18	5.29	52.1	0.009	0.016	>50	2030-11-04	
3-RF-101-05	5.49	2.41	2019-10-18	5.17	5.14	0.011	0.006	>50	2030-11-04	
3-RF-101-06	5.49	2.41	2019-10-18	5.12	5.13	0.014	-0.002	>50	2030-11-04	
3-RF-101-07	5.49	2.41	2019-10-18	5.38	5.25	0.006	0.026	>50	2030-11-04	
3-RF-101-08	5.49	2.41	2019-10-18	5.23	5.12	0.022	0.022	>50	2030-11-04	
3-RF-101-09	5.49	2.41	2019-10-18	5.13	5.10	0.002	0.006	>50	2030-11-04	

Line 2-RF-102 | Reflux | A312 TP316 | t_nom 3.91 mm | t-min 2.16 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
2-RF-102-01	3.91	2.16	2019-10-18	3.66	3.55	0.013	0.022	>50	2030-11-04	
2-RF-102-02	3.91	2.16	2019-10-18	3.65	3.53	0.012	0.024	>50	2030-11-04	
2-RF-102-03	3.91	2.16	2019-10-18	3.68	3.65	0.010	0.006	>50	2030-11-04	
2-RF-102-04	3.91	2.16	2019-10-18	2.83	1.94	0.067	0.176	expired	immediate	< t-min; gauge photo attached
2-RF-102-05	3.91	2.16	2019-10-18	2.88	1.92	0.159	0.190	expired	immediate	< t-min; gauge photo attached

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
2-RF-102-06	3.91	2.16	2019-10-18	2.74	1.92	0.160	0.162	expired	immediate	< t-min; gauge photo attached
2-RF-102-07	3.91	2.16	2019-10-18	2.82	1.86	0.073	0.190	expired	immediate	< t-min; gauge photo attached

Line 4-LA-104 | L/R exchanger, lean side | A106 Gr.B | t_nom 6.02 mm | t-min 3.18 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-LA-104-01	6.02	3.18	2019-10-18	5.16	5.02	0.037	0.028	>50	2030-11-04	
4-LA-104-02	6.02	3.18	2019-10-18	4.79	4.55	0.052	0.048	26.5	2030-11-04	
4-LA-104-03	6.02	3.18	2019-10-18	5.23	5.20	0.027	0.006	>50	2030-11-04	
4-LA-104-04	6.02	3.18	2019-10-18	5.49	5.34	0.025	0.030	>50	2030-11-04	
4-LA-104-05	6.02	3.18	2019-10-18	4.71	4.37	0.058	0.067	17.7	2030-11-04	
4-LA-104-06	6.02	3.18	2019-10-18	5.38	5.17	0.032	0.042	47.8	2030-11-04	
4-LA-104-07	6.02	3.18	2019-10-18	5.15	4.92	0.038	0.046	38.2	2030-11-04	
4-LA-104-08	6.02	3.18	2019-10-18	4.88	4.63	0.046	0.050	29.3	2030-11-04	
4-LA-104-09	6.02	3.18	2019-10-18	4.61	4.37	0.048	0.048	25.0	2030-11-04	
4-LA-104-10	6.02	3.18	2019-10-18	4.63	4.32	0.060	0.061	18.6	2030-11-04	

Line 4-RA-104 | L/R exchanger, rich side | A106 Gr.B | t_nom 8.56 mm | t-min 3.81 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
4-RA-104-01	8.56	3.81	2022-09-16	6.61	6.33	0.076	0.162	15.5	2027-11-04	
4-RA-104-02	8.56	3.81	2022-09-16	7.04	6.84	0.060	0.093	32.5	2027-11-04	
4-RA-104-03	8.56	3.81	2022-09-16	7.70	7.67	0.065	0.053	>50	2027-11-04	
4-RA-104-04	8.56	3.81	2022-09-16	7.31	6.98	0.109	0.131	24.2	2027-11-04	
4-RA-104-05	8.56	3.81	2022-09-16	7.12	6.74	0.119	0.164	17.8	2027-11-04	
4-RA-104-06	8.56	3.81	2022-09-16	6.70	6.41	0.076	0.143	18.2	2027-11-04	
4-RA-104-07	8.56	3.81	2022-09-16	6.04	5.61	0.104	0.210	8.6	2027-11-04	gauge photo attached
4-RA-104-08	8.56	3.81	2022-09-16	7.09	6.90	0.093	0.111	27.9	2027-11-04	

Line 2-ST-101 | Reboiler steam | A106 Gr.B | t_nom 3.91 mm | t-min 2.29 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
2-ST-101-01	3.91	2.29	2019-10-18	3.59	3.42	0.018	0.034	33.6	2030-11-04	
2-ST-101-02	3.91	2.29	2019-10-18	3.34	3.19	0.025	0.030	30.3	2030-11-04	
2-ST-101-03	3.91	2.29	2019-10-18	3.68	—	—	—	—	—	inaccessible – no reading
2-ST-101-04	3.91	2.29	2019-10-18	3.52	3.50	0.011	0.004	>50	2030-11-04	
2-ST-101-05	3.91	2.29	2019-10-18	3.27	3.22	0.024	0.010	38.6	2030-11-04	
2-ST-101-06	3.91	2.29	2019-10-18	3.66	3.66	-0.003	0.000	>50	2030-11-04	

Line 3-CW-101 | Amine cooler CW | A106 Gr.B | t_nom 5.49 mm | t-min 2.79 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
3-CW-101-01	5.49	2.79	2019-10-18	4.91	4.79	0.022	0.024	>50	2030-11-04	
3-CW-101-02	5.49	2.79	2019-10-18	4.98	4.69	0.025	0.057	33.1	2030-11-04	
3-CW-101-03	5.49	2.79	2019-10-18	4.87	4.63	0.031	0.048	38.7	2030-11-04	
3-CW-101-04	5.49	2.79	2019-10-18	5.20	5.22	0.008	-0.004	>50	2030-11-04	
3-CW-101-05	5.49	2.79	2019-10-18	5.14	5.19	0.010	-0.010	>50	2030-11-04	
3-CW-101-06	5.49	2.79	2019-10-18	5.01	4.91	0.019	0.020	>50	2030-11-04	

Line 3-CW-102 | Amine cooler CW | A106 Gr.B | t_nom 5.49 mm | t-min 2.79 mm

CML	t_nom (mm)	t-min (mm)	Prev. date	Prev. (mm)	Current (mm)	CR LT (mm/y)	CR ST (mm/y)	RL (y)	Next due	Remark
3-CW-102-01	5.49	2.79	2019-10-18	4.85	4.77	0.025	0.016	>50	2030-11-04	
3-CW-102-02	5.49	2.79	2019-10-18	4.17	4.09	0.050	0.016	26.2	2030-11-04	
3-CW-102-03	5.49	2.79	2019-10-18	4.27	4.12	0.049	0.030	27.0	2030-11-04	
3-CW-102-04	5.49	2.79	2019-10-18	4.50	4.29	0.043	0.042	35.2	2030-11-04	
3-CW-102-05	5.49	2.79	2019-10-18	4.45	4.35	0.036	0.020	43.9	2030-11-04	

Sign-off	Name	Function	Date	Signature
Prepared	Marcus Chen	lead UT technician, SNT-TC-1A UT/MT/PT/VT Level II; CAN/CGSB-48.9712 UT Level II	2024-11-14	_____
Reviewed	David Park	Level III / Quality Manager, SNT-TC-1A UT Level III	2024-11-14	_____