QSCP Corporate Asset Integrity

Corporate Summary

No.	Status	Date
QSCP-CI-GAP-NR-2018	Issued	10.09.2018

Gap Assessment - Werk Niederrhein against QSCP-CIS-001 Rev 0

Assessment Objective and Scope

This document, authored by Daniel Hartmann and Dr. Helen Marchetti, summarizes the gap assessment of current piping integrity practices at Werk Niederrhein against the requirements of QSCP-CIS-001 Rev 0. The assessment evaluates the alignment of local risk-based inspection intervals and data management protocols with the newly adopted corporate integrity standard.

Review of Local Inspection Framework

Current site practices are governed by NR-PFE-21-2015, NR-GBU-21-2015, and NR-PK-21, which establish a 5-year cycle for external inspections and strength tests. While these documents utilize NDT for strength verification, QSCP-CIS-001 Rev 0 introduces mandatory RBI-based intervals and specific data requirements for Fitness-for-Service (FFS) assessments performed by qualified engineers. Furthermore, NR-PP-21 Rev 1 defines a hotspot program for insulated austenitic lines operating above 60 °C, utilizing PT every 30 months at insulation windows and aluminum-foil wrapping under new insulation.

Identified Gaps and Compliance Requirements

To achieve full compliance with QSCP-CIS-001 Rev 0, Werk Niederrhein must transition from the fixed intervals defined in NR-PFE-21-2015 to an RBI methodology that remains within code maxima. A comprehensive CML re-baseline is required to meet the corporate data standards. Although NR-PK-21 and NR-GBU-21-2015 address regulatory safety requirements, the site must integrate the corporate requirement for FFS evaluations to be validated by a qualified engineer as part of the ongoing integrity management cycle.

Sign-off	Name	Function	Date	Signature
Prepared	Daniel Hartmann	Integrity Engineer, QSCP Corporate Asset Integrity, based at Werk Niederrhein	10.09.2018	_____
Prepared	Dr. Helen Marchetti	Corporate Asset Integrity Manager, P.Eng.	10.09.2018	_____